

## **5.0 EXISTING STORM WATER MANAGEMENT FACILITIES**

The 2007 Terry Fox Drive EA and Functional Design Report identified the need to provide storm water management at the northeasterly end of the Terry Fox Drive project limits. The storm water management of runoff for Terry Fox Drive from station 15+475 to 16+500 has been described in detail in the Design Brief for Morgan's Grant Phase 10A Stormwater Management Facility (report dated January 2006 by CCL/IBI). Minor runoff (for the 10-year event) will be conveyed to the Morgan's Grant Phase 10A facility, while major runoff from the area will be conveyed to the existing drainage course on the south side of Terry Fox Drive. The quality and quantity requirements for the facility (consisting of runoff from Terry Fox Drive and Morgan's Grant Phase 10A) are also covered by the 2006 report. This facility has now been constructed.